

Creating cross-over vehicles: Defining and combining vehicle classes using shape grammars

SETH ORSBORN,¹ JONATHAN CAGAN,¹ RICHARD PAWLICKI,² AND RANDALL C. SMITH²

¹Department of Mechanical Engineering, Carnegie Mellon University, Pittsburgh, Pennsylvania, USA

²Research & Development Division, General Motors, Detroit, Michigan, USA

(RECEIVED June 29, 2005; ACCEPTED February 14, 2006)

Abstract

In the push for new vehicle designs, the distinctions between vehicle classes are quickly becoming blurred. We use shape grammars to quantify the differences between vehicle classes through the application of class-specific rules and the constraint of rule applications to within parametric ranges determined for each class. This allows for the development of new vehicle forms that clearly fall within a class or purposefully cross over the boundaries of classes and mix rules and ranges to create unique and interesting cross-over vehicles.

Keywords: Cross-Over Vehicle; Design Language; Shape Grammars; Vehicle Design

1. INTRODUCTION

The vehicle design process is constantly being improved upon. Previously, it took over 5 years to bring a car from inception to showroom. Now, with the use of various computational tools and refined design processes, the time has been cut in half. That alone is still too long to meet the dynamic requirements of the consumer public. Currently, the best vehicle designers are able to take their creations straight from their imagination to CAD programs like Alias AutoStudio, bypassing the sketching phase. Even in these instances, there are still many different design ideas that must be produced before the concept can be narrowed down to the one that will be brought on to the prototype phase. This paper develops a means to understand and accelerate the designs of such vehicles.

Shape grammars have been used for over two decades as computational design tools for representing design artifacts. Shape grammars are production systems created by taking a sample of the whole for which one is trying to write a language (Stiny, 1980). From this sample a vocabulary of shapes can be written that represent all the basic forms of that sample. By defining the spatial relationships

between those forms and how the forms are related to each other, shape rules can be written. A shape rule consists of a left side and a right side. If the shape in the left side matches a shape in a drawing then the rule can be applied, and the matching shape changes to match the right side of the rule. The shape rules allow the addition and subtraction of shapes, which in the end are perceived as shape modifications. These shape rules, combined with an initial shape, produce a shape grammar that represents the language of the design (Stiny, 1980). Shapes themselves can exist as points, lines, planes, volumes, or any combination thereof (Stiny, 1980). All shape generation must start with an initial shape: a point, a coordinate axis, and so forth. If the grammar is going to end, it must end with a terminal rule, which prevents any other rules from being applied after it. This forces closure in the rule sequence.

There are multiple ways to drive a shape grammar. The simplest is to utilize labels and markers. Labels are typically alphanumeric characters attached to a shape. Markers are similar to labels, but they are symbols attached to a shape. In both cases, they are used to limit which rules can and cannot be applied to the shape. If an appropriate marker or label exists, then a rule can be applied. The terminal rule typically removes all labels and markers. Another way to drive the grammar is through shape recognition. Shape recognition is able to drive the grammar in the same way that labels and markers do, but it is broader in that it allows the

Reprint requests to: Jonathan Cagan, Department of Mechanical Engineering, Carnegie Mellon University, Scaife Hall, 5000 Forbes Avenue, Pittsburgh, PA 15213, USA. E-mail: cagan@cmu.edu

rules to be applied to a parametric range of a shape. It allows any shape within predefined allowable limits to be recognized by the rule and thus allows the rule to be applied. If the shape in the left-hand side of the rule exists and is recognizable, then the rule can be applied. The difficulty is that the rule must recognize a parameterized shape, that is, a similar shape regardless of scaling, rotation, or other allowable modifications. A parametric shape grammar allows for the modification of similar shapes and the removal and placement of parametric shapes.

The advantage of labels and markers is that the grammar can force certain rules to be applied and prevent nonapplicable rules from being used. When developing a form that is generally the same, this enables all the aspects of the form to be created in a proper order with proper relationships. It was shown in the coffee maker grammar (Agarwal & Cagan, 1998) that all coffee makers fundamentally have the same components. By utilizing labels, it was ensured that each of these components would be created and placed in a reasonable relationship with the other components. The coffee maker grammar utilized rules that applied to more than one view: top, side, and front. The labels enabled changes to be made in multiple views that were sensible, and then the final shapes could be abstracted to three-dimensional (3-D) models. The labels drove the grammar and prevented the rules from creating forms that did not hold the necessary functionality. For example, labels enforced an important relationship among the three main components: the filter, the water storage unit, and the base unit. Labels prevented the base unit from being above the water storage unit, so that the final coffee maker design could be usable.

The Buick brand shape grammar (McCormack et al., 2004) also used labels to drive the rules, but it was not limited by these labels. Buick is an easily identifiable brand with many consistent features in the front view, so these could be label driven. However, the forms of these features were found to be different, depending on when the vehicle was created. By utilizing shape recognition, the shape grammar could modify components of the vehicle without being limited by the labels. At the same time, the modifications could be constrained to keep the form within the limits derived for the brand. This allowed curves to be pushed and stretched to create new forms, but never outside the Buick brand bounds. By applying these modifications to the individual components, the whole vehicle form would be new, but still fall within the Buick brand language, and be recognizable as a Buick. Other applications of shape grammars include architectural floor plans (Stiny & Mitchell, 1978), Chinese ice-ray lattice windows (Stiny, 1977), and Harley-Davidson branding (Pugliese & Cagan, 2001). This paper merges the Harley-Davidson and Buick grammar approaches to create a vehicle grammar by adding rules and parametric ranges to specify the vehicle class language.

The first shape grammars utilized only straight lines. The computations for these rules were defined to allow for the

interaction and recognition of these lines (Krishnamurti, 1980). Because the world is not composed of only straight lines, the next obvious step was to recognize curves and curved shapes (McCormack & Cagan, 2002). However, there was still a limitation in that up to this point all the shape grammars that have dealt with lines and curves were only in a single planar coordinate system. Some grammars have been created that use 3-D shapes, for instance, to build Wright style houses (Koning & Eizenberg, 1981). To continue to progress in the applicability of shape grammars, the next step is to move toward implementing parametric curves and surfaces in three dimensions.

This paper takes the idea of the Buick brand shape grammar and the Harley-Davidson motorcycle grammar as models to investigate a new area of application of shape grammars. Rather than limiting the grammar to a comparison of brands, which had been shown effectively with previous grammars, it was decided that an understanding of the differences between classes of products, in this case vehicles, and the possibilities to merge them would be a useful application in the current trend of cross-over innovation. Vehicles were chosen specifically for several reasons:

1. they are 3-D forms,
2. they are composed of characteristics that are universally found in all vehicles, and
3. such a parametric shape grammar would allow for the application of labels and shape recognition.

2. MOTIVATION

Cross-over vehicles take styling cues from two or more vehicle classes. There are commonly accepted characteristics that belong to specific classes, such as, coupes only have two doors. However, many of the characteristics of vehicles occur in multiple classes of vehicles and it is the parametric range of these characteristics that determine within which class the vehicle falls. To design cross-over vehicles, it is necessary to first understand the definition of the separate vehicle classes. Once a vehicle class has been clearly defined, the task of merging classes becomes elementary.

Shape grammars offer the ability to quickly produce multiple vehicle designs that fall within desired constraints. A carefully extracted vocabulary provides a basis on which an infinite number of future designs can be derived. Sample vehicles from the classes of coupes, pickups, and SUVs are used to build this shape grammar. By choosing the most appropriate sample, a shape grammar is derived that is able to produce not only the vehicles from which it was derived, but also an infinite number of additional designs. By imposing spatial constraints and understanding the parametric range for each characteristic within its vehicle class, the classes themselves can be defined and then combined to produce




Fig. 1. Rule 9 demonstrating the use of labels; F, front; S, side; R, rear.




Fig. 2. Rule 11 demonstrating the use of labels in a parametric rule.

Table 1. Vehicle sample used to derive shape grammar

	Coupes	SUVs	Pickups
1	Acura RSX	Acura MDX	Chevrolet Silverado
2	Audi TT	BMW X3	Dodge Ram
3	BMW M3	BMW X5	Ford F150
4	Chevrolet Cavalier	Chevrolet Suburban	Ford Ranger
5	Dodge Stratus	Ford Escape	GMC Canyon
6	Ferrari 456M	Ford Excursion	GMC Sonoma
7	Ferrari 612 Scaglietti	Ford Expedition	Toyota Tacoma
8	Ford Mustang	Ford Explorer	
9	Honda Accord	Hyundai Santa Fe	
10	Honda Civic	Kia Sportage	
11	Hyundai Tiburon	Land Rover Free Lander	
12	Mercedes Benz C	Land Rover Range Rover	
13	Mercedes Benz CLK	Mazda Tribute	
14	Mitsubishi Eclipse	Mercedes Benz ML	
15	Toyota Celica	Mitsubishi Montero	
16		Mitsubishi Montero Sport	
17		Porsche Cayenne	
18		Suzuki Grand Vitara	
19		Toyota Land Cruiser	
20		Toyota RAV4	
Control group	BMW 645i	Volkswagen Touareg	Mitsubishi L200




Fig. 3. The example shape modification rule.

unique cross-over vehicles. The vehicles produced with this shape grammar can then be used as fodder for the imagination of the designer. Although many of the designs may not be inspiring, the intention is to produce some truly innovative designs. The designer can then choose to pursue the idea further as is, modify it, or just forget it.




Fig. 4. The vehicle characteristics included in the shape grammar: (1) front wheels, (2) rear wheels, (3) front wheel well, (4) rear wheel well, (5) front fender, (6) rear fender, (7) front bumper, (8) rear bumper, (9) front windshield, (10) rear windshield, (11) grill, (12) headlight, (13) hood, (14) roof, (15) trunk, (16) taillight, (17) rocker, (18) door, (19) front side window, (20) rear side window, (21) door handle, (22) ground, and (23) belt line.




Fig. 5. Example rules for understanding the grammar.

The move to label shape grammars is a large step on its own, which needs to be taken incrementally. The path was previously laid out by Stiny (1992). This set the foundation for us to create a grammar in three dimensions. The first step is to create a shape grammar that functions in multiple coordinate systems. The benefit of creating such a shape grammar is that it can then be utilized to understand the relationship between different 3-D objects. In this application, a shape grammar is built to capture vehicle classes. It was decided initially that to capture an automobile's form, three views should be taken into account: front, side, and rear. The front and rear views share the same coordinate system, but they look at different characteristics of the vehicle. The key here is to understand which characteristics appear in more than one view and how to link them together through their rule applications. For simplicity, each vehicle is assumed to be symmetric about the longitudinal plane, so only half of the front and rear view is drawn. The top view could be included in future work.

Labeled curves provide the most direct way to drive the automobile grammar. Because the automobile is composed of certain characteristics, labels are used to ensure that each of these characteristics is added. The labels themselves are not enough to constrain the rule applications. In this grammar, a combination of parametric shape recognition and labels are required for many of the rule applications. For example, in rule 9, if only label 3 exists, the top of the front wheel well can be added (Fig. 1). However, if label 3 exists and there is a related parametric curve, then rule 11 should be used (Fig. 2), which adds in the lower part of the front wheel well. Note that the letters following the rule numbers represent the view: F, S, and R are the front, side, and rear, respectively.

Labeled curves drive the insertion of the characteristics of the vehicle, but markers and shape recognition are used for the modification of these shapes. The shape modification rules can be applied to any curve that still has the unlabeled end points. For example, in rule F (Fig. 3), a




Fig. 6. The initial shape.

curve can be rotated about one of its end points. This rule can be applied to any curve that has two nonlabeled, or labeled, end points. There are additional constraints to this rule application, such as rule H must be applied first, which are discussed in further detail later.

3. VEHICLE SAMPLE

As stated previously, vehicles were chosen from three known classes: coupes, pickups, and SUVs. The requirements were that each vehicle have a blueprint that included the front, side, and rear views; that each of the views be isometric (or as close as possible); and that the three views complement

each other parametrically. Table 1 indicates the sample vehicles for each class.

All vehicles chosen were the most recently available model year. All pickups chosen were extended cab models. This eliminated outliers in the set. It was also foreseen that crew cab models would be able to be drawn from the rules used to create SUVs. The coupes were all standard coupes. Any vehicles considered to be anomalies in their class were not chosen for the vocabulary.

Three vehicles, one from each class, were separated out as a control group. To confirm that the shape grammar was constructed properly, these vehicles that were not used to derive the vocabulary were built with the completed grammar (Table 1).

4. CHARACTERISTICS

Because one of the intentions of this shape grammar was to define the vehicle classes, it was necessary to carefully consider which vehicle characteristics should be used. Through discussion with vehicle designers, it was determined that




Fig. 7. The ground rules.

the following vehicle characteristics are the most relevant in the early stages of vehicle design (see Fig. 4): (1) front wheels, (2) rear wheels, (3) front wheel well, (4) rear wheel well, (5) front fender, (6) rear fender, (7) front bumper, (8) rear bumper, (9) front windshield, (10) rear windshield, (11) grill, (12) headlight, (13) hood, (14) roof, (15) trunk, (16) taillight, (17) rocker, (18) door, (19) front side window, (20) rear side window, (21) door handle, (22) ground, and (23) belt line.

The belt line, which starts at the bottom of the A-pillar and runs along the bottom of the side windows to the trunk, is an important characteristic. There are no specific rules for the belt line, but it is built using a combination of the related characteristics: the hood, side windows, and trunk.

Each characteristic is defined by a curve or set of curves. These curves were captured manually through the following process:

1. A vehicle's blueprint was imported as an image plane into Alias DesignStudio.
2. Each characteristic was traced using Bezier curves (four control points), except wheels that use circles.
3. The minimum number of curves was used to capture the characteristic accurately.
4. This was done for each of the three views.

The curves defining the characteristics were then used as the vocabulary with which the shape grammar rules were written.

5. SHAPE GRAMMAR RULES

With the vocabulary extracted from the characteristics, 70 rules were written. The rules were written in such a way as to follow a logical progression in the creation of the vehi-




Fig. 8. The wheel rules.




Fig. 9. The wheel well rules.




Fig. 10. The rocker rule.

cle, not to minimize the number of rules. This method of progression, although not exactly what an automotive designer would use, was confirmed to be appropriate by an automotive designer. Sixty-one of these rules are vehicle characteristic rules that are used to build the actual vehicle characteristics. These rules are driven by labels. Nine of these rules are general modification rules for curves. These 9 rules can be applied to any curve, in any view, that still has the appropriate marker at its end points. These rules are also constrained by the allowable parameters for the curves to which they are applying, which is described in further detail later in this paper. Each vehicle characteristic rule starts with a number followed by a letter that represent the view (F for front, S for side, R for rear). Thus, the views are connected by their rule number, and the application of a rule is carried through the different views. For example, if rule 1 positions the ground, then rule 1F will be the front instantiation of rule 1S. Linking rules together has been shown to be an effective way to implement a grammar with more than one component (Agarwal & Cagan, 1998; Knight, 2003).

There are constraints in each rule application:

1. A grey shape or label on the left-hand side indicates that that curve or label must not exist for the rule to be applied. This constraint, although not standard, is necessary to prevent certain rules from being applied multiple times and still keep continuity of the design process.
2. A grey label on the right-hand side indicates a removed label.
3. Parametric ranges prevent certain instances, for example, the rocker cannot be lower than the ground.
4. The general modification rules are applicable to any shape in any view, as long as it still has its end-point markers.
5. Vertical modification of a shape in a view must match a vertical modification of a shape in its related view. For example, when rule 21 (Fig. 5) is applied label 8 must have the same vertical position in both the front and side views.

6. If a curve is modified, the related curves must be modified accordingly. Connected end points are not allowed to disconnect, unless indicated by the rule. For example, if rule E (Fig. 5) is applied to the upper curve of a round headlight, the lower curve must also then be modified accordingly.

Because of the labels, the vehicle characteristic rules must follow in a general order, although for some characteristics the order can vary somewhat. However, once a characteristic is placed, the modification of that characteristic is only limited by the parametric constraints and the termination rule. This allows the designer a great degree of flexibility in modifying an initial design.

The rules were first built using just the forms from the coupe vehicle class. The pickup and SUV classes were then visited, which forced some rules to be added for some of the characteristics. This helped to define the differences between the vehicle classes. This set up a methodology for future extensions to other vehicle classes. Each rule in the shape grammar and its constraints is now explained in detail. There are 61 vehicle characteristic rules that place the actual vehicle forms. These can then be modified by the 9 general modification rules.

5.1. Vehicle characteristic rules

The initial shape (Fig. 6) is the relative coordinate system. The front and rear horizontal are linked and the vertical in all three views is linked.

The ground rules (Fig. 7) are used to set the placement of the wheels. Rule 1 sets the wheel width, rule 2 sets the wheel base, and rule 3 inserts the ground below the vehicle.

The wheel rules (Fig. 8) are used to build the front and rear wheels. Rule 4 inserts the front tire of a specified diameter. Rule 5 inserts the rear tire, which may or may not be the same diameter as the front tire. Rule 6 inserts the rim, which is a diameter that is less than the diameter of the tire.

The wheel well rules (Fig. 9) insert the front and rear wheel wells. Rules 7 and 8 position the front and rear wheel wells, respectively, in relation to their wheels. Rules 9 and




Fig. 11. The fender rules.




Fig. 12. The hood rules.

10 insert the upper part of the wheel well. In these rules, as in all other rules that apply to more than one view, the vertical length of the curve must be the same in both views, that is, the bottom marker in rule 9 must have the same vertical coordinate in the front and side views. Rules 11 and 12 insert the lower part of the wheel well, which begins to define where the bumpers will be.

The rocker rule (Fig. 10) joins the front and rear wheel wells in the side view.

The fender rules (Fig. 11) insert the front and rear fenders. Rules 14 and 15 position the fender with respect to the wheel well, and rule 16 inserts the curve of the fender that is seen from only the front and rear views. Rules 17, 18, and 50 insert the fender. Rule 50 is used specifically for SUVs and pickups. Class-specific rules like this one will be addressed in more detail later in the article.

The hood rules (Fig. 12) insert the hood. Rule 19 sets the intersection of the front windshield, hood, and A-pillar; it is positioned with respect to the front fender. Rule 20 inserts a hood in which the inner hood line is connected, and rule 21 inserts a hood in which the inner hood line is floating. Note that in both rules in the front view the hood must come all

the way to the center of the vehicle as indicated by the spatial relationship with the initial shape.

The grill rules (Fig. 13) insert the front grill. Rule 22 allows the front bumper to be attached directly to the hood. This is commonly used in coupes, in which it is followed by rule 30 (Fig. 14) that allows the grill to be inserted into the front bumper. Each grill rule inserts label 18, which holds the position for the headlight insertion rule. Rules 23–28 insert different types of grills. The odd numbered rules show the grill from the side view and the even numbered rules represent the grill as just a single curve in the side view. This is to delineate between grills that wrap around the front of the vehicle to the side and grills that are not visible from the side view.

The front bumper rules (Fig. 14) insert the front bumper. Rules 29 and 52 insert upper front bumpers; the former has a connected horizontal line, and the latter has a disconnected horizontal line. When used sequentially, multiple front bumper forms can be inserted. Rule 30 is used in the instance that a grill is inserted into the front bumper, and rule 31 inserts the lower part of the front bumper and connects it to the front wheel well.













Rule 22F •8 → •9	Rule 22S •8 → •9 •18	Rule 22R
Rule 23F •8 → 	Rule 23S •8 →  •18	Rule 23R
Rule 24F •8 → 	Rule 24S •8 →  •18	Rule 24R
Rule 25F •8 → 	Rule 25S •8 →  •18	Rule 25R
Rule 26F •8 → 	Rule 26S •8 →  •18	Rule 26R
Rule 27F •8 → 	Rule 27S •8 →  •18	Rule 27R
Rule 28F •8 → 	Rule 28S •8 →  •18	Rule 28R

Fig. 13. The grill rules.

The front windshield rule (Fig. 15) inserts the front windshield and sets the position for the front side window with label 7. The form is basically the same for all vehicles but it can be modified using the shape modification rules detailed later.

The roof rule (Fig. 16) inserts the roof. This rule is used on all vehicles, but the distance between labels 10 and 11 varies greatly.

The rear windshield rules (Fig. 17) insert one of three different rear windshields.

The trunk rules (Fig. 18) insert the section between the rear windshield and the rear bumper. In this set, label 17

sets where the tail light will be inserted. Rule 36 inserts a traditional trunk, and rule 49 inserts a pickup bed. Rule 56 inserts the bottom half of a hatch, which can be modified using rule 37.

The rear bumper rules (Fig. 19) insert the rear bumpers. Rules 38 and 57 insert traditional upper rear bumpers. Rule 54 inserts a step in the rear bumper, commonly found on midsize SUVs. Rules 39 and 51 insert lower rear bumpers.

The door rules (Fig. 20) insert and modify side doors. Rules 40 and 58 insert the side door, with a variation in the rule depending on whether the side curve has already been drawn. The curve between labels 6 and 7 in the rear view is




Fig. 14. The front bumper rules.




Fig. 15. The front windshield rule.




Fig. 16. The roof rule.

often inserted with the trunk. Rule 55 allows a change in the belt line, a curve found commonly on large SUVs and pickups. Rule 41 inserts a curve representing a rear side door.

The door handle rule (Fig. 21) inserts a standard door handle that can then be modified.

The front side window rules (Fig. 22) insert the side windows. Rule 43 is traditionally used with vehicles that do




Fig. 17. The rear windshield rules.

not have a rear side door, and rule 44 is used with vehicles that do have a rear side door. Rule 44 also sets label 16, which enables another side window to be inserted farther back.

The rear side window rule (Fig. 23) inserts a rear side window between the front side window and the rear windshield.

The headlight rules (Fig. 24) insert and modify the headlights. Rule 46 inserts a standard four-sided headlight that can be modified to curves using rule 59 or the general modification rules. If more than one label 18 was created when inserting the front bumper, rule 61 must be applied before the headlight can be inserted.

The taillight rules (Fig. 25) insert the taillights. Rule 47 is for coupes, and rule 53 is for pickups and SUVs. The difference again lies in the fact that certain curves are not visible from the rear view on pickups and SUVs. Rule 60 can be applied to change the four-sided taillight to two round taillights.

5.2. General modification rules

Figure 26 shows the general modification rules. These rules can be applied to any curve in any view, as long as the curve still has its end-point markers. There are constraints, in that a curve that exists in more than one view must nec-

essarily have the same vertical dimension. The horizontal dimension in the front (or rear) and side views may not be the same. Rule A takes two curves and divides them into three similar curves. This is commonly used on fenders and wheel wells. Rule B changes two curves to one or vice versa. Rule C changes the arc through which a curve sweeps. Rule D scales a curve proportionally, and rule E scales a curve nonproportionally and is used quite frequently. Rule F rotates a curve about one end point. Rule G changes the length of a line. Rule H enables a labeled or unlabeled point to be moved. This rule must first be applied to relocate one or more end points of a curve before rules C through G can be applied. This forces attached curves to remain attached at their end points throughout curve modifications. Rule H is also useful in the positioning of hoods, headlights, and taillights. Rule I is the terminal rule and removes all end points of the curves. Once this rule is applied throughout the vehicle, no more rules can be applied and the vehicle design is completed.

5.3. Rule application example

To better understand the application of these rules, and the purpose of the labels, the following example is given. This is a progression of the insertion of the grill and front fender, with modifications, for the Ferrari 612 Scaglietti. It is again




Fig. 18. The trunk rules.

noted that there is symmetry in the front and rear views, so that only half of the front and rear views will be produced and shown.

Figure 27a shows a finalized hood. Label 8 at the end of the hood allows for the start of the grill. Then, rule 22 is applied (Fig. 27b), to allow the front bumper to connect directly to the hood. This changes label 8 to label 9 and inserts label 18, which will eventually be used to insert the headlights. Rule 29 is applied (Fig. 27c), which builds the upper part of the front bumper. Rule 30 is applied (Fig. 27d), which adds a small part of the front bumper and inserts label 8, which allows the grill to be inserted into the front bumper. Rule 23 is used to insert the grill (Fig. 27e). Note that another label 18 is inserted. Now, the user must choose to eliminate one of the label 18s because the headlight insertion rule can only be applied with one label 18. The lower label 18 is removed using rule 61, and the grill curves are modified using rules H and E (Fig. 27f). Then, rule 31 is applied (Fig. 27g), which attaches the front bumper to the front wheel well. This also removes all labels associated

with the front bumper and grill to eliminate the possibility of another set being added.

6. DEFINING VEHICLE CLASSES BY CHARACTERISTICS

There are two different ways to define the vehicle classes. The first is to examine the derived rules. Certain rules are applicable to only certain classes. This enables the designer to limit the design to a certain class by choosing specific rules to keep the vehicle within that class. These class-specific rules are summarized in Table 2.

All other rules are universal and apply to every class of vehicle. It is important to note that the rules not in the list in Table 2 are applied to vehicle characteristics universally. These are characteristics that all classes of vehicles share, which may only be differentiated through parametric curve modification rules.

The second way to define vehicle classes is to examine differences between classes and define ranges of the param-




Fig. 19. The rear bumper rules.

eters of the characteristics themselves. When a rule is universally applied, the differentiation of the characteristics is purely through the curve modification rules. Although all three classes share many of the same characteristics, which are applied using the same rules, the range in which the characteristics fall is limited within each vehicle class.

Each curve in the shape grammar is represented as a Bezier curve with four control points. The following examples include plots of the control points. Note that these are not plots of the curves themselves, but of their four control points. The curves are considered from two different coordinate systems, the global coordinate system and the local coordinate system (Fig. 28). The global coordinate system takes the point at which the front wheel touches the ground as its coordinate axis; the coordinate axis is seen in the side view of the initial shape (Fig. 6). This is consistent for all vehicles. The local coordinate system takes a common end point as the coordinate axis. The two different frames of

reference enable us to discern differences between the parametric ranges from two different points of view.

Figures 29–38 display detail for five curves to understand the parametric ranges that are allowed for universally applied rules: front fender, side, hood, front windshield, and grill. Control points for coupes, pickups, and SUVs are represented. Each figure shows the allowable range for the control points to stay within the designated vehicle class.

Figures 29 and 30 are graphs of the allowable ranges of the front fender, which is characteristic 5 in the side view of Figure 4. The front fender viewed from the side view is composed of two curves. In Figure 29 these two curves are joined to represent the front fender. Coupe fenders are taller and longer (i.e., a greater arc). Coupe fenders also have the largest range. SUV fenders are lower and flatter than coupe fenders, and they are vertically distinct from coupe fenders. Pickup fenders overlap the other two classes and almost entirely contain the SUV class.




Fig. 20. The door rules.




Fig. 21. The door handle rule.

In Figure 30 the coupe fenders are much lower than the SUV fenders and pickup fenders, which are almost identical. This shows that globally there is an accepted height for a coupe fender that is different for SUV and pickup fenders.

It should be observed that the lower the pickup fender globally, the greater the arc locally; that is, the closer the fender gets to the ground, the more it resembles a coupe fender, and the higher it gets off the ground, the more it flattens




Fig. 22. The front side window rules.




Fig. 23. The rear side window rules.




Fig. 24. The headlight rules.




Fig. 25. The taillight rules.

out. This allows a differentiation to be made between small and large pickups.

Figures 31 and 32 refer to the side curve (characteristic 19) in the front and rear views of Figure 4. In Figure 31 the coupe sides have a much shallower ascent with a rounder curve and are generally shorter in height. Again, there is no overlap between coupe and SUV sides, which gives another differentiation between the classes. Pickup sides have the height of SUV sides, but they can have the curvature of coupe sides.

In Figure 32 the coupe sides have a much narrower and lower range than SUV or pickup sides. SUV and pickup sides line up almost exactly, although SUV sides are taller and higher. This also shows how wide a vehicle is at the point above the belt line. Coupes are narrower overall in comparison to SUVs and pickups. This enables a limitation in the width of a vehicle with this characteristic, with respect to its class. It is interesting to note, in general, that the higher and wider the vehicle is, the flatter the curvature of the side.

Figures 33 and 34 refer to the hood curve (characteristic 13) as seen in the side view of Figure 4. In Figure 33 the coupe hoods are much longer and can be taller than SUV and pickup hoods. Pickup and coupe hoods both have a greater curvature than SUV hoods, which are typically flatter. This shows that the range for SUV hoods is quite small and falls almost entirely within the coupe hood range. It is interesting to note that in general coupe hoods have a fairly consistent curvature whereas SUV hoods are sharp at the front and flatten out toward the windshield.

In Figure 34 the pickup and SUV hoods line up, and both are much higher than coupe hoods and initially farther back. Coupe hoods have the longest horizontal range and do not vary as much vertically. This sets a clear global differentiation between classes with respect to hoods. This can help in the development of new vehicles and can even be studied more closely to find further significance.

Figures 35 and 36 refer to the front windshield curve (characteristic 9) in the side view of Figure 4. In Figure 35 the SUV windshields are much steeper and have no overlap in their range with the shallower, longer coupe windshields. This shows a clear distinction between the traditionally allowable ranges for coupe and SUV windshields. Pickup windshields fall tightly within the SUV windshield range, but they have their lower end overlapping slightly with coupe windshields.

In Figure 36 the coupe windshields are much lower than SUV and pickup windshields, and the range varies mostly horizontally. SUV windshields have the largest vertical range, with a move back as height increases. Pickup windshields vary slightly vertically, but not much horizontally. Although the positioning and length varies throughout the ranges and classes, the curvature of the front windshields remains fairly consistent.

Figures 37 and 38 refer to the grill curve (characteristic 11) in Figure 4. In Figure 37 the coupe grills are much shorter in height than pickup and SUV grills. They can even be negative with respect to the local coordinate system, if located in the front fender. Pickup grills are as tall as SUV grills, but only as long as coupe grills. SUV grills




Fig. 26. The general modification rules.




Fig. 27. An example of rule progression.

Table 2. Class-specific rules

Rule Number	Class-Specific Rule Application
18	Draws the rear fender for coupes only
50	Draws the rear fender for SUVs and pickups
23 and 24	Grill rules only used on coupes
52	Front bumper rule for pickups and SUVs only
30	Allows the grill to be inserted into the front bumper, only for coupes
48	Rear windshield rule used only on pickups and some SUVs
36	Trunk rule for coupes only
37	Trunk rule for coupes and SUVs only
49	Bed rule for pickups only
56	Trunk (hatch) rule for SUVs
54	Puts step on SUV rear bumper
51	Rear bumper for SUVs and pickups only
57	Rear bumper for SUVs and pickups only
40	Does not work with pickups
55	Puts curve in beltline in front door, only on SUVs
41	Adds rear side door, SUVs only
43	Rear side window for coupes only
44	Rear side window for pickups and SUVs
45	Rear window for SUVs only
59	Headlight rule for coupes only
53	Taillight rule for SUVs and pickups
60	Taillight rule for coupes only




Fig. 28. Global versus local coordinate systems.

Front Fender Curves - Global




Fig. 30. The front fender curve global coordinate system. The grey area surrounded by a symbol shows the allowable range for the control points to stay within the designated vehicle class.

have the greatest range, from short and upright to tall and long, but they stay entirely in the positive side. This shows where the limitations of the classes are with respect to the grill.

In Figure 38 the coupe grills are much lower than the other two and come farther forward, because of nose length and location within the bumper. SUV and pickup grills are similar in height range and horizontal average, but SUV grills have a broader horizontal range. Both come farther back than coupe grills, because of shorter noses. Again, a clear distinction is made between the classes. It should be noted that SUV and pickup grills tend to curve consistently, whereas coupe grills curve sharply at the beginning or the end. This is the inverse of what occurs in the hood (Fig. 33). This shows that where the form changes from vertical to horizontal in the front end is in the grill for coupes and in

Front Fender Curves - Local




Fig. 29. The front fender curve local coordinate system. The grey area surrounded by a symbol shows the allowable range for the control points to stay within the designated vehicle class.




Fig. 37. The grill curve local coordinate system. The grey area surrounded by a symbol shows the allowable range for the control points to stay within the designated vehicle class.

Volkswagen Touareg. To test if the shape grammar properly represents the language of design for coupes, pickups, and SUVs, each of these vehicles was generated using this grammar. The completed designs are shown with the front and rear views mirrored in Figures 42–44.

Next, to test the vocabulary of the shape grammar, an existing vehicle was designed that overlapped between the classes. A Ford Focus (Fig. 45) was chosen because it used rules from both the coupe and the SUV to build it. This vehicle was not part of the original sample, but we were able to draw it from the derived vehicle vocabulary using 50 rule applications.

The front end of the Ford Focus was created using the same rules for coupes. However, once the windshield was done, the roof was created using the parametric range for SUVs. Then, the rear windshield and trunk were created from SUV rules. The real innovation here was with the taillights. By using rule H (translation of a point), label 17 could be moved to a unique position by the belt line. The taillight was then inserted and constrained by the geometry already in place. The details are given in the following paragraph.

Figure 46 shows the complete generation of the Ford Focus. The process starts with the initial shape (Fig. 46a). Rules 1–3 are applied to insert the ground with the chosen wheel base and wheel width (Fig. 46b). Then rules 4–6 are applied to add the tires and the rims (Fig. 46c). Rules 7–10

add the upper part of the wheel wells, and rules E and H are applied to modify the shape of the upper wheel wells. Rules 11 and 12 add the lower wheel wells, followed by rules E and H to modify their shape. Rule 13 adds the rocker between the front and rear wheel wells (Fig. 46d). Rules 14–18 add the fenders and are followed by rules H, C, E, and F to modify their shapes (Fig. 46e). Rule 19 sets the base of the hood and rule 20 adds the hood (Fig. 46f). Rule 26 adds the grill, followed by rules H and G to modify the curve; rules 29 and 30 add the upper front bumper; rule 27 adds a lower grill, modified by rules H, E, and F; and rule 31 attaches the front bumper to the front wheel well (Fig. 46g). Rule 32 adds the windshield; rule 33 adds the roof; and rule 35 adds the rear windshield, which is then modified by rules H and F (Fig. 46h). Rule 56 adds the trunk, and rules 38 and 39 put in the rear bumper (Fig. 46i). Rule 58 inserts the door; rule I removes label 15 to prevent a rear door; rule 42 inserts the door handle, which is then modified by several applications of rules H and E; and rule 43 inserts the side windows, which are then modified using rules H and E (Fig. 46j). Rule 46 inserts the headlight, which is modified using rules H, B, and E (Fig. 46k). Rule H moves label 17 for the taillight; rule 47 inserts the taillight; and rules H, B, and E change the shape of the taillight (Fig. 46l). Rule I removes all the end points to give the finished vehicle shown in Figure 45, where the front and rear views are mirrored.

Grill Curve 1 - Global




Fig. 38. The grill curve global coordinate system. The grey area surrounded by a symbol shows the allowable range for the control points to stay within the designated vehicle class.

